





PLAN NORTH

 1
 A1-1
SECOND FLOOR PLAN
 SCALE: 1/4" = 1'-0"

GENERAL NOTES:

1. ALL PIPING AND/OR CONDUITS TO BE PARALLEL OR PERPENDICULAR TO BLDG. LINES
2. WHERE ACCESSORIES OR EQUIPMENT ARE MOUNTED TO WALLS PROVIDE ADDITIONAL STUDS AND/OR BLOCKING AS REQ'D TO SECURELY ANCHOR & SUPPORT THE ITEM.
3. MOUNT ALL LIGHT SWITCHES, CONTROLS, FIRE EXTINGUISHERS, ETC. AT 4'-0" ABOVE FINISHED FLOOR - TYP.
4. ALL COLORS AS SELECTED BY OWNER. SUBMIT SAMPLES FOR APPROVAL.
5. PROVIDE 3-5# ABC FIRE EXTINGUISHER & WALL CABINET (GROUND FLOOR) & 1-5# ABC FIRE EXTINGUISHER & WALL BRACKET (MECH LOFT)
6. ALL GYP. BD. WALLS 1/2" FIBER REIN. GYP. BD. ; ALL GYP. BD. CLGS. 5/8" UNLESS OTHERWISE NOTED.

WALL LEGEND:

- | | |
|---|---|
|  | TYP. EXTERIOR WALL:
4" BRICK VENEER, 1" AIR SPACE, 'TYVEK' HOUSE WRAP OVER 1/2" EXTERIOR PLYWD SHEATHING OVER 2X6 WOOD STUD @ 16" O.C. INSULATE W/ 6" FOIL FACED R-19 BATT INSULATION. FINISH INTERIOR FACE OF WALL W/ 1/2" FIBER REIN. GYPSUM BOARD. NOM. 10" - ACTUAL 10-1/2" |
|  | TYP. INTERIOR WALL:
1/2" FIBER REIN. GYPSUM BOARD EACH SIDE OF 2X4 WOOD STUD @ 16" O.C. - NOM. 5" - ACTUAL 4-1/2" |
|  | TYP. INTERIOR WALL - BRG. WALL:
BRG WALL - SEE STRUCTURAL |

REVISIONS:

PROJECT #:

1115-30

DATE:

11.06.09

DRAWN BY:

DESIGNER:

CHECKED BY:



**Ledford
Engineering &
Planning, LLC**

SEAL:



JML
Architecture · Planning
Construction Administration

3992 Davies Manor
Bartlett, Tennessee 38133
PH: 901/371-8698

SECOND FLOOR PLAN

2009 CAPITAL FUND RECOVERY PROGRAM
 NEW OFFICE BUILDING
 AR 37S02450109
 WEST MEMPHIS HOUSING AUTHORITY
 WEST MEMPHIS, ARKANSAS

SHEET NUMBER:

A1-2

OF SHEETS

DESCRIPTION: